

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PAT per
PS

API Well Number: 15-063-21306-00-00

Spot: SESESE

Sec/Twnshp/Rge: 10-11S-31W

382 ~~330~~ feet from S Section Line,

330 feet from E Section Line

Lease Name: WALZ

396 Well #: 1

County: GOVE

Total Vertical Depth: 4630 feet

Operator License No.: 4656

Op Name: DAVIS PETROLEUM, INC.

Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4629	0	275 SX
SURF	8.625	379	0	195 SX <u>150.48</u>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/20/2008 10:00 AM

Plug Co. License No.: 33369

Plug Co. Name: XTREME WELL SERVICE, INC.

Proposal Rcvd. from: MIKE KASSELMAN

Company: DAVIS PETROLEUM, INC.

Phone: (620) 793-3051

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel.
Top down plug.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/20/2008 1:50 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 379' w/195 sxs cement.
4 1/2" production casing set at 4629' w/275 sxs cement.
TD 4630'. PBTd 4625'. Stage collar at 2525' w/350 sxs.
Connected to 4 1/2" production casing - pumped 50 sxs cement with 500# hulls - 9 sxs gel and 170 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Connected to 8 5/8" surface casing - pumped 10 sxs cement.
Max. P.S.I. 100#. S.I.P. 0#.
Casing ruptured below base of cellar. Well had been squeezed.

Perfs:

Top	Bot	Thru	Comments
4525	4528		
4513	4518		
4310	4313		
4250	4253		

INVOICED

DATE 12-23-08

INV. NO. 2009060902

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 03 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #43975.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)


CM

PAT

STATE KANS COUNTY GOVE
FIELD KEARNS (LANSING/CHEROKEE)
OPER DAVIS PET
WELL 1 WALZ
API 15-063-21306-0000
SPUD 12/27/1989
DTD 4630 LTD FTD MISS

WELL CLASS DO
STATUS OIL
COMP 01/27/1990
PSTD

10-11S-31W
SE SE SE
330FSL 330FEL SEC



LOC 1 1/4 MI S CAMPUS, KS

Petroleum Information

IP OIL WELL - IP NOT AVAILABLE
PROD ZONE: LANSING INTERVAL NOT RPTD

EL: 2986 GR
NO LOGS RPTD

CSGS: 8 5/8 @ 379 CMT
RAN PROD CSG

DRLG COMP 1/5/90 RIG REL 1/5/90

PERFS: LANSING PERF
INTERVAL & TREATMENT NOT RPTD

NO CORES OR DSTS RPTD

FILED CONFIDENTIAL W/STATE

OPER ADDRESS: RT 1, BOX 183-B, GREAT BEND, KS 67530

CONTR: L D DRLG

GEOL: KIM SHOEMAKER

KS 10-070390

Copyright 1990 Petroleum Information Corporation