

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR John O. Farmer, Inc. API NO. 15-065-21,548-00-00
 ADDRESS P.O. Box 352 COUNTY Graham
Russell, KS 67665 FIELD Ernst Northwest
 **CONTACT PERSON Margaret A. Schulte LEASE Klenk
 PHONE (913) 483-3144

PURCHASER Mobil Oil Corporation WELL NO. #6
 ADDRESS P.O. Box 900 WELL LOCATION NW SE NE
Dallas, TX 75221 990 Ft. from the east Line and
 990 Ft. from the south Line of
 the NE/4 SEC. 18 TWP. 9S RGE. 23W

DRILLING CONTRACTOR John O. Farmer, Inc.
 ADDRESS P.O. Box 352
Russell, KS 67665


PLUGGING CONTRACTOR _____
 ADDRESS _____
 TOTAL DEPTH 3990' PBTD _____

SPUD DATE 12-14-81 DATE COMPLETED 12-22-81

ELEV: GR 2408' DF 2411' KB 2413'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Report of all strings set — surface, intermediate, production, etc. (New)/(~~XXXX~~) casing.



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC
 KGS
 MISC. _____

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20	208'	Common	165	
Production	7-7/8"	4-1/2"	10 1/2	3989'	50-50 Pozmix	150	10% Salt
			DV Tool @ 2060'		w/425 sxs. cement		2% Gel


LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	SSB Jets	3899-3905

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
2000 gal. 15% NE	3899-3905

RECEIVED
 STATE CORPORATION COMMISSION
 3-15-82
 MAR 15 1982
 CONSERVATION DIVISION
 Wichita, Kansas

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
February 25, 1982	Pumping		
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water
	30 bbls.	---	% 0 bbls.
Disposition of gas (vented, used on lease or sold)		Producing interval (s)	
---		3899-3905	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.



Name of lowest fresh water producing stratum Unknown Depth 100'
 Estimated height of cement behind pipe Top

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
	0	1110		<u>Log Tops</u>
Shale & Sand	1110	1605		
Sand & Shale	1605	1805	Anhydrite	2054 (+359)
Sand	1805	2057	Heebner	3705 (-1292)
Red Bed	2057	2093	Toronto	3732 (-1319)
Anhydrite	2093	2135	Lansing	3746 (-1333)
Shale & Shells	2135	2365	B/KC	3970 (-1557)
Shale & Lime	2365	2580	T.D.	3991 (-1578)
Shale	2580	2815		
Lime & Shale	2815	3140		
Shale & Lime	3140	3305		
Lime & Shale	3305	3495		
Shale & Lime	3495	3802		
Lime & Shale	3802	3990		
Lime				
DST #1 3770-3802 Tool open 45-45-45-45 - fair blow Rec: 130' muddy water IFP: 58-71 FFP: 87-106 BHP: 164-155 DST #2 3885-3910 Tool open 45-45-45-45 - good blow Rec: 66' gassy oil cut mud 124' gassy muddy oil IFP: 68-97 FFP: 116-126 BHP: 252-252 DST #3 3920-50 Tool open 30-30-10 - weak blow, 17 min. Rec: 10' mud - few specks of oil FP: 38-48 IBHP: 116				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Russell SS,

John O. Farmer III OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS vice-president FOR John O. Farmer, Inc.
 OPERATOR OF THE Klenk LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. #6 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 12th DAY OF March 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) John O. Farmer III
John O. Farmer III
 SUBSCRIBED AND SWORN TO BEFORE ME THIS 12th DAY OF March 1982

Margaret A. Schulte
 NOTARY PUBLIC
 Margaret A. Schulte



MY COMMISSION EXPIRES: January 27, 1985