


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

GRAHAM County, Sec. 20 Twp. 9 Rge. (E) 23 (W)  
Location as "NE/CNWxSWx" or footage from lines SW NE SW  
Lease Owner A. L. ABERCROMBIE, INC.  
Lease Name ERNST Well No. 1  
Office Address 801 UNION CENTER - WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) OIL  
Date well completed 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved MARCH 15 19 71  
Plugging commenced MARCH 21 19 71  
Plugging completed APRIL 6 19 71  
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3950 Feet  
Show depth and thickness of all water, oil and gas formations. 3985 RT KLC


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	260'	NONE
				4 1/2"	3984'	1017'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3955' - 3750' - PLUG  
3750' - 3725' - SAND  
3725' - 3689' - 3 SACKS CEMENT  
3689' - BASE - PUMPED 3 SACKS OF HULLS, 15 SACKS OF MUD AND 110 CUBIC FEET OF 50/50 POZMIX WITH 6% GEL.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor SANTA FE PIPE & SUPPLY, INC.  
Address BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T. L. NUTT (employee of owner) or (XXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
BOX 562 - GREAT BEND, KANSAS 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 71  
July 31, 1974  
Mary M. Guesnier Notary Public.

