

15-065-03256-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

GRAHAM County, Sec. 21 Twp. 9 Rge. 23 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner SPECTER PIPE & SUPPLY COMPANY

Lease Name PRESCOTT Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2-22-58 19

Application for plugging filed 1-2-66 19

Application for plugging approved 1-3-66 19

Plugging commenced January 9, 1966 19

Plugging completed January 16, 1966 19

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. NICHOLS, MORELAND, KANSAS

Producing formation Kansas City Depth to top 3965' Bottom 3973' Total Depth of Well 3975' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1375'	none
				5 1/2"	3972'	3335'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged, back with sand to -3965-feet, dumped 5- sacks cement.  
Set a Rock Bridge at 550- feet, dumped 20- sacks cement.  
Dumped 20- sacks cement at 250-feet, put ten sacks cement on top.

STATE CORPORATION COMMISSION  
JAN 24 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY NO. 457

Address R.Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas COUNTY OF Russell, ss.

Specter Pipe & Supply (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W.L. Nichols*

(Address) \_\_\_\_\_, 1966

*Wilma M. Lindahl*  
Notary Public.



NOTE SIGNATURE


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- **AMERADA PETROLEUM CORP.**  
 Farm- **B. F. Prescott** No. **1**

SEC. **21** T. **9** R. **23W**  
 SW SW SE

Total Depth. **3975'**  
 Comm. **2-11-58** Comp. **2-22-58**  
 Shot or Treated.  
 Contractor. **Glenn W. Peel**  
 Issued. **5-17-58**

County **Graham**  
**KANSAS**



Elevation. **2425'** **DF**

Production. **139 BOPD, NW**

**CASING:**

**8 5/8"** — **1375'** cem.  
**5 1/2"** — **3972'** cem.

Figures indicate Bottom of Formations.

surface soil	45
shale & sand	775
shale	860
sand	1050
sand & shale	1380
red bed & sand	1890
red bed	2025
Anhydrite	2055
shale	2100
shale & lime	2725
lime	2735
lime & shale	3020
lime, shells & shale	3105
lime & shale	3320
shale, lime & shells	3395
lime & shale	3580
lime	3975
Total Depth	

**TOPS: SCOUT**

Anhydrite	2025
Heebner	3711
Toronto	3735
Lansing	3745
Base Kansas City	3965

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 APR 18 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas