

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 21 Twp. 9S Rge. (X) 23 (W)

Location as "NE/CNW/SW" or footage from lines. 100' W. of S 1/2 NE NW

Lease Owner Rains & Williamson Oil Co., Inc.

Lease Name LEYBURN-EDWARDS Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-22 19 67

Application for plugging filed 3-22 19 67

Application for plugging approved 3-22 19 67


Plugging commenced 3-22 19 67

Plugging completed 3-22 19 67

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Moreland, Kansas

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3985 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210.14'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 600'. Cemented w/20 sacks through drill pipe. Mudded back to 210', pushed plug and hulls to 210' and cemented through drill pipe with 20 sacks; 2 sacks cement in rat hole. Plugging completed at 1:00 P.M., 3-22-67.

RECEIVED
STATE CORPORATION COMMISSION
3-27-67
MAR 27 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains

1425 Wichita Plaza - Wichita, Kansas

(Address) 67

24 day of March, 19 67

SUBSCRIBED AND SWORN to before me this

24

day of

March

(Address)


67

My commission expires March 3, 1970

Mary J. Brown

Mary J. Brown

Notary Public.



ROTARY DRILLING LOG

Operator: Rains & Williamson
 Oil Co., Inc.
 #1 LEYBURN-EDWARDS
 100' W. of S½ NE NW
 Section 21-9S-23W
 Graham County, Kansas

Contractor: Rains & Williamson
 Oil Co., Inc.
 Commenced: 3-16-67
 Completed: 3-22-67
 2433' KB
 Remarks: Set 8-5/8" surface
 casing at 210.14'
 w/160 sacks GL-3.

Formations

Surface soil & shale	105'
Shale	212'
Shale and shells	800'
Shale	1440'
Shale and Red Beds	1565'
Sand	1775'
Shale	2033'
Anhydrite	2067'
Shale	2580'
Shale and Lime	2805'
Lime	2890'
Shale and Lime	3135'
Lime and Shale	3777'
Lime	3985'
Rotary Total Depth (D & A)	3985'

RECEIVED
 STATE CORPORATION COMMISSION

MAR 27 1967

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains

 Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 24th day of March, 1967.

Mary J. Brown

 Mary J. Brown Notary Public

My Commission Expires:
 March 3, 1970

