15-065-21586-0000


Form CP-4
Rev. 12-15-80

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 21 TWP. 9 RGE. 23 ~~E~~W
Location as in quarters or footage from lines:
50' W/SE/SE/NW



Locate Well correctly on above Section Platt.

Lease Owner Frontier Oil Co.
Lease Name Goddard Well No. #1
Office Address 1437 N. Franklin - Russell, Ks. 67665
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed
Application for plugging filed
Plugging commenced June 30, 1982
Plugging completed July 26, 1982
Reason for abandonment of well or producing formation
Depleted
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation Depth to top bottom T.D. 3925'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	~~217'~~ 224'	NONE
				4 1/2"	3917'	1421.42'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 3850' and four (4) sacks cement.
Shot pipe @ 3150', 2500', 2000', 1800', 1600', 1500' and 1420'.
Pulled thirty-six joints of 4½" casing.
Squeezed well with five (5) sacks hulls, fourteen (14) sacks gel, seventy (70) sacks 50/50 pozmix cement with 6% gel and 3% calcium chloride, eleven (11) sacks gel and seventy (70) sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
JAMES W. ROCKHOLD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
(Address) JAMES W. ROCKHOLD - Box 698 - Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 12 day of August, 1982

Margaret Prosser
Notary Public.

My Commission expires NOTARY PUBLIC - State of Kansas MARGARET PROSSER My Appt. Exp. 4-16-86

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1982
CONSERVATION DIVISION
Wichita, Kansas