

3-6

4-032300

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-193-20-445-0000

C N2 NW SE 1/4 SEC. 24, T10, R33 W
2310 feet from S section line
1980 feet from E section line

RECEIVED
KANSAS CORP COM
1998 MAR 20
3-20-98

Operator license# 30742

Lease: F&J Farms Well # B-1

Operator: Palomino Petroleum, Inc.

County: Thomas 152,26

Address: 4924 SE 84th Street
Newton, Kansas 67114-8827

Well total depth 4685 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 298 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging-contractor: D.S.&W. Well Service License# 6901

Address: Claflin, Kansas 67525

Company to plug at: Hour: P.M. Day: 6 Month: March Year: 1998

Plugging proposal received from: Kent

Company: D.S.&W. Well Service Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs gel.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 6 Month: March Year: 1998

Actual plugging report: 8 5/8" set at 298' w/200 sxs cwc. 4 1/2" set at 4684' w/250 sxs.
D.V. at 2620' with 375 sxs cwc. Prod. Perfs 4211' - 4212'. Squeezed 4 1/2" with 40 sxs
cement blend with 500# hulls mixed in, followed by 10 sxs gel, followed by 100 sxs cement
blend to Max. P.S.I. 1000#. Held. Cement in braden head and annulus. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE MAR 23 1998

INV. NO. 50293