

8-16

4-061099

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-193-20,664 - 0000
100' N. of
SE SE NW /4 SEC. 29, 10 S, 33 W
3070 feet from S section line
2970 feet from E section line

Operator license# 5420

Lease: Cooper Well # 1-29

Operator: White & Ellis Drilling, Inc.

County: Thomas 153.27

Address: P.O. Box 48848
Wichita, Kansas 67201-8848

Well total depth 4716 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 359 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: White & Ellis Drilling, Inc. License# 5420

Address: Wichita, Kansas 67201

Company to plug at: Hour: 5:45 A.M. Day: 16 Month: August Year: 1997

Plugging proposal received from: Judy

Company: White & Ellis Drilling, Inc. Phone: 316-263-1102

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 8:45 A.M., Day: 16, Month: August, Year: 1997

Actual plugging report:

- 1st. Plug at 2640' w/25 sxs. - Anhydrite 2619' - 2647'.
- 2nd. Plug at 1725' w/100 sxs. - Dakota 1419' - 1719'.
- 3rd. Plug at 410' w/40 sxs. - Surface pipe to 359'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.

8-26-97

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 3119 GL

I did [] / did not [X] observe the plugging.

INVOICED

[Signature]
PX (agent)

Form CP-2/3

DATE 8-28-97

INV. NO. 48870

8-16