

7-14

4-041590

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,581-0000

N2 N2 SW /4 SEC. 28 , 10 S, 33 W  
2310 feet from S section line  
3360 feet from E section line

Operator license# 30031 Lease Gustafson well # 1

Operator: Ellsworth Systems, Inc. County Thomas

Address: 922 Union Center Building Well total depth 4695 feet  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 251 feet  
w/170 sxs.

152.58

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas - Oakley, Kansas

Company to plug at: Hour: 10:00A.M Day: 14 Month: July Year: 94

Plugging proposal received from: Ron Schroeder

Company: Ellsworth Systems, Inc. Phone:                     

Were: 4 1/2" casing set @ 4692' w/475 sxs. cement. Perfs. @ 4595' -  
4610'. Casing cement from bottom to top - verified with bond log.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[      ], Part[ X ], None[      ]

Completed: Hour: 12:00P.M, Day: 14, Month: July, Year: 94

Actual plugging report: 4 1/2" casing. Pumped in 25 sxs. cement with  
300# hulls followed with 15 sxs. gel, followed with 100 sxs. 60/40  
pozmix - 10% gel. Max. 1200#. 8 5/8" S.P. - Pressured-up to 600#  
P.S.I.

Remarks: Casing cemented - verified with bond log.

Condition of casing(in hole):GOOD X BAD      Anhy.plug:YES X NO     

Bottom plug(in place):YES X, CALC     , NO      Dakota plug:YES X, NO     

Plugged through TUBING     , CASING X. Elevation:                      GL RECEIVED

I did not observe the plugging.

**INVOICED**

DATE JUL 28 1994

INV. NO. 40906

7-14

*Dennis J. Hamel*  
STATE CORPORATION COMMISSION

(agent) 26 1994  
7-26-94

Form CP-2/3 CONSERVATION DIVISION  
Wichita, Kansas