

4- 060323

7-2

145  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,594-0000

S2 NE SE /4 SEC. 32 , 10 S , 33 W  
1650 feet from S section line  
660 feet from E section line

Operator license# 5184

Lease Rein well # 1

Operator: Shields Oil Producers, Inc.

County Thomas

Address: Shields Building  
Russell, Kansas 67665

Well total depth 4630 feet <sup>150.47</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Shields Drilling Company License# 5655

Address: Russell, Kansas 67665

Company to plug at: Hour: 3:30A.M. Day: 3<sup>rd</sup> <sup>rd</sup> Month: July Year: 92

Plugging proposal received from: Burt Berry

Company: Shields Drilling Company Phone: 913-483-3141

Were: Order 200 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per. sx.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 3:30A.M., Day: 3<sup>rd</sup>, Month: July, Year: 92

Actual plugging report:    

1st. plug at 2700' w/25 sxs. - Anhydrite 2671' - 2731'.

2nd. plug at 1790' w/100 sxs. - Dakota 1486' - 1786'.

3rd. plug at 300' w/40 sxs. - Surface pipe to 250'.

4th. plug at 40' w/10 sxs.

15 sxs. in Rathole.

10 sxs. in Mousehole.

Remarks: Allied Cementing

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES    , CALC    , NO X Dakota plug: YES X NO    

Plugged through TUBING    , CASING    . Elevation: 3186 GL    

I did[     ] / did not[ X ] observe the plugging.

DATE JUL 30 1992

INV. NO. 35842

*[Signature]*

*[Signature]*

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1992

CONSERVATION DIVISION  
Wichita, Kansas