

6030433

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_

Operator: State of Kansas

Name & Address: Fee Fund Re-entry

Cons. Div. of K.C.C.

202 W 1st St. Wichita, Kansas

67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated OWWO Re-entry

Plugging Contractor Sun Cement Co. License Number \_\_\_\_\_

Address Oakley Kansas

Company to plug at: Hour: PM Day: 21 Month: 3 Year: 19 85

Plugging proposal received from Duane Rankin & Carl Goodrow

(company name) State Cons. Div. of K.C.C. (phone) \_\_\_\_\_

were: 8 3/8 act @ 315' Run 2 3/8 tubing to T.D. spot plugs to

surface. Order 225 sq Cement mix. 50/50 poz 6% gel 3% cc

37 sq gel. Sun Cement Wellrock water truck

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:55PM Day: 21 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Tag bottom with 2 3/8 tubing Circulate 37 sq

gel to surface. Displace 75 sq Cem. mix. laydown tubing

from 1620' to 820' displace 75 sq Cem mix. laydown tubing

to 356' displace 50 sq Cem. mix laydown tubing displace

25 sq Cem. mix and circulate to cellar Plug Complete

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: \_\_\_\_\_ MAY 10 1985

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

CONSERVATION DIVISION  
Wichita, Kansas

Signed Carl Goodrow  
(TECHNICIAN)

5-10-85  
mmx