

4 060239

8-28

358

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,569-0000
100' N
SE SE SE, SEC. 32, T 10 S, R 33 W/E

430 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30606

Lease Name Carl Reins Well # 1-32

Operator: Murfin Drilling Co.
Name & Address: 250 N. Water Suite 300
Wichita, KS 67202

County Thomas 155.35

Well Total Depth 4780 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 30606

Address Wichita, KS

Company to plug at: Hour: 1:15PM Day: 28 Month: August Year: 19 91

Plugging proposal received from Lloyd Delett

(company name) Murfin Drilling Co. (phone)

were: Order 200 sxs. 60/40pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXX

Operations Completed: Hour: 1:15PM Day: 28 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2680' with 25 sxs. Anhydrite 2668-2694'

2nd plug at 1780' with 100 sxs. Dakota 1477-1777'

3rd plug at 375' with 40 sxs. Surface pipe to 323'

4th plug at 40' with 10 sxs.

Rathole with 15 sxs. mousehole with 10 sxs.

Remarks: Allied Cementing (If additional description is necessary, use BACK of this form)

RECEIVED STATE CORPORATION COMMISSION

9-5-91 SEP 05 1991

INVOICED (XXXXXX did not observe this plugging.)

DATE 9-13-91

INV. NO. 33128

Signed Herb Deines (TECHNICIAN)

8-28 NOV 20 1991