

4-061191

7-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-193-20,669-0000
NW SW SE /4 SEC. 35, 10 S, 33 W
990 feet from S section line
2310 feet from E section line

Operator license# 3988

Lease: James 'AS' Well # 1

Operator: Slawson Exploration Co., Inc.

County: Thomas 154.80

Address: 200 N. Harvey - Suite #1412
Oklahoma City, OK 73102

Well total depth 4763 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 315 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 9:30 A.M. Day: 30 Month: July Year: 1999

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour 12:30 P.M., Day: 30, Month: July, Year: 1999

Actual plugging report:

1st. Plug at 2650' w/25 sxs cement. Anhydrite 2635' - 2660'.

2nd. Plug at 1750' w/100 sxs cement. Dakota 1439' - 1738'.

3rd. Plug at 365' w/40 sxs cement. Surface pipe to 315'.

4th. Plug at 40' w/10 sxs cement.

15 sxs in rathole.

Remarks: Allied Cementing.

Condition of casing in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 3138 GL

I did[] / did not[] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION

8-5-99
AUG - 5 1999

[Signature]
(agent)

Form CP-2/3

INVOICED

DATE AUG 06 1999

INV. NO. 60122

CONSERVATION DIVISION
Wichita, Kansas

(R)