

6-100444

11-17

126
#

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,580-0000

SW SW SE /4 SEC. 33, 10 S, 33 W
490 feet from S section line
2310 feet from E section line

Operator license# 03966

Lease Clark well # 1

Operator: Wanker Oil

County Thomas

153.72

Address: RR 2, Box 14
WaKeeney, Kansas 67672

Well total depth 4730 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 256 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 08241

Address: Russell, Kansas 67665

Company to plug at: Hour: ? Day: Month: Year:

Plugging proposal received from: John Collins

Company: Emphasas Oil Operations phone:

Were: **spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2640 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1765 feet " 100 " Mousehole: 10 sacks

3rd plug @ 300 feet " 40 "

4th plug @ 40 feet " Wiper plug & 10 sx cmt

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:00 pm, Day: 17, Month: November, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3167 GL, Anhydrite depth: 2640 - 2673 feet

Did NOT penetrate Arbuckle, cemented by Allied

I did [] / did not [X] observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED
DATE 12-5-91
33939

Rob. S.