

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21,956-0000

TECHNICIAN'S PLUGGING REPORT

NW-NW-NE, Sec. 18, T 9 S, R 230 W/E
230 feet from N section line
2310 feet from W section line

Operator License # 5135

Lease Name HLENK Well # 11

Operator: JOHN O FARMER
Name & Address P.O. BOX 252
RUSSELL, KANS.
67665

County GRAHAM
Well Total Depth 3900 feet 126.75
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor JOHN O FARMER License Number 5135 TAG # 220

Address P.O. BOX 252, RUSSELL, KANS. 67665

Company to plug at: Hour: 8:00 PM Day: 15th Month: APRIL Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO HERMAN MICK

(company name) JOHN O FARMER (phone) 913-483-2144

were:

8 5/8" - 215' SP. CUL #150 SK COMMON GEL - CA-CL (BY ALLIED CNT.)
ORDER 195 SK 50/50 Pozmix GEL - CA-CL - 1 SK CELLO FLAKE AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.
ELY. 2319 - ANH. 1984 - NO AIRBUCKLE - NO CIRCULATION PROBLEMS.

Signed Marius Schmidt
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15 PM Day: 20th Month: APRIL Year: 1984

ACTUAL PLUGGING REPORT

ORDERED 195 SK 50/50 Pozmix GEL - CA-CL - AND 8 5/8" PLUG - 1 SK CELLO FLAKE.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

1st Plug @ 2010' ET #125 SK CNT.
2nd Plug @ 1120' ET #100 SK CNT #1 SK CELLO FLAKE.
3rd Plug @ 270' ET #50 SK CNT.
4th Plug Solid Dodge @ 40' ET #0 #10 SK CNT.
10th In Pat #16 (circulate)

Remarks:

CEMENTED BY ALLIED CNT.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated and that I (did / did not) observe this plugging.

Signed Marius Schmidt
(TECHNICIAN) DOIC

INVOICED

DATE 4-30-84

INV. NO. 1300

4-20