

To: **6 031527**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-10 349 R
API NUMBER 15- 065-01,026-0001

NE NE NE SEC. 18, T 9 S, R 23 W/EX
4950 feet from S section line
330 feet from E section line

Lease Name Albertson Well # 1
County Graham 127.40
Well Total Depth 3920 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 171

TECHNICIAN'S PLUGGING REPORT
Operator License # 5135
Operator: John O. Farmer Inc.
Name & Address: Box 352
Russell, Ks. 67665

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx
Other well as hereinafter indicated

Plugging Contractor Plainville Well Service License Number 7251
Address Plainville, Ks.

Company to plug at: Hour: PM Day: 10 Month: April Year: 19 91

Plugging proposal received from Lawrence Eichman
(company name) J.O. Farmer (phone)
were: 8 5/8 set at 171 w/115 w/115 sks cwc. Re-enter to check

plugs. Then, re-plug.
Order 300 sks 60/40 poz 10% gel 300 lbs. hulls. Allied Cement co. water trucks.

RECEIVED
4-25-91
APR 25 1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 7:00PM Day: 10 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Drilled to 650 established the fact we were out of the old bore hole and drilling virgin shale. Circulation was lost when we drilled by area of the base of original plug indicating to us we had communicated with old hole. the decision was made to plug hole. Tripped pipe, removed collars and bit ran in open ended tubing to 620. circulated cement to surface; laid down tubing.

There was some loss of cement in the hole indicating movement into old bore hole. Squeezed 8 5/8 w/total of 300 sks cement blend w/300 lbs. hulls mixed into max psi 1000lb. Remarks: Close in psi 500 lbs. Calculated cement to 1300. Elev 2391 KB. (if additional description is necessary, use BACK of this form.)

INVOICED
DATE 5-7-91
INV. NO. 31772
4-10 AUG 12 1991

Signed Carl Goodrow (TECHNICIAN)