

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21806-00-01 ² *OK*
Spot: NWNENE Sec/Twnshp/Rge: 18-9S-23W
330 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: KLENK Well Number: 10
County: GRAHAM Total Vertical Depth: 3946 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 258 160 SX CMT
Production: Size 5.5 feet: 3945 200 SX CMT
Liner: Size feet: 128.25

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/07/2001 8:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 700# hulls - 18 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/07/2001 11:30 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:
Pumped down 5 1/2" casing with 50 sxs cement with 500# hulls, followed with 18 sxs gel, followed with 200 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
8 5/8" S.P. pressured up to Max. P.S.I. 1000#.

RECEIVED
8-15-01
AUG 15 2001
KCC WICHITA


Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

District: 04 Signed Dennis L. Hamel
100 (TECHNICIAN)

AUG 13 2001

INVOICED
DATE 8-15-01
INV. NO. 2002060242

JOHN O. FARMER, INC.
 P.O. BOX 352
 RUSSELL, KS 67665
 CONTR COMPANY TOOLS
 GEOL _____
 #10 KLENK
 CTY GRAHAM
 FIELD ERNST NW
 ELV 2380 KB SPD 7/10/83 CARD ISSUED 9/15/83 IP P 10 BOPD
 API 15-065-21,806 LKC 3864-3870
 18-9-23W
 NW NE NE



LOG	Tops	Depth/Datum
ANH	2034+ 346
HEEB	3670-1290
TOR	3696-1316
LANS	3714-1334
RTD	3946-1566

8 5/8 " 258 / 160SX; 5 1/2 " 3945 / 200SX
 DST (1) 3855-75 (LANS) / 45-45-45-45, 240' GIP, REC 62' G & OCM, SIP 141-146#, FP 27-27 / 29-34#
 DST (2) 3895-3920 (LANS) / 30-30-0-0, REC 5' OCM, ISIP 25# - NO FSIP, FP 21-21#
 MICT - CO, PF (LKC) 3864-70, W / 4 SPF, AC 2000G, SWB LD, T&R, POP, P 10 BOPD, 8/23/83