

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21690-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 18-9S-23W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: KLENK Well Number: 7  
County: GRAHAM Total Vertical Depth: 3960 feet

Operator License No.: 5135  
Operator Name: FARMER, JOHN O., INC.  
Address: PO BOX 352  
RUSSELL, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.62 feet: 220  
Production: Size 5.5 feet: 3959  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

128.70

10/17

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/17/00  
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/17/2000 11:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 220' w/160 sxs cwc. 5 1/2" set at 3959' w/150 sxs.  
PBSD 3925'. D.V. Tool at 2043' w/450 sxs cwc.  
Prod. Perf 3874' - 3918'.  
Squeezed 5 1/2" w/260 sxs cement with 500# hulls mixed into Max. P.S.I. 1000#. Held.  
Test 8 5/8" to Max. P.S.I. 500#. Full.

RECEIVED  
STATE CORPORATION COMMISSION  
10-26-00  
OCT 26 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks:

Plugged through:

District: 04

HO.

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

DATE

10/26/00

INV. NO.

2001060890

Form CP-2/3

OCT 23 2000

JOHN O. FARMER, INC.

P.O. BOX 352

#7 KLENK

18-9-23W  
NW NE SE


RUSSELL, KS 67665

CONTR JOHN O. FARMER, INC.

CTY GRAHAM

GEOL

FIELD ERNST NW



ELV 2390 KB SPD 10/16/82 CARD ISSUED 12/23/82 IP P 30 BOPD

API 15-065-21,690

LANS 3874-3918 OA

LOG	Tops	Depth/Datum	
ANH		2019 ± 371	8 5/8 " 220'160SX; 5 1/2 " 3959'150SX
HEEB		3684-1294	DST (1) 3865-85 (LANS) / 45-45-60-60, 120' GIP, REC 10' FO, 30' OCM, SIP 125-173#, FP 28-28 / 38-38#
TOR		3708-1318	
LANS		3724-1334	DST (2) 3905-25 (LANS) / 45-45-45-45, 380' GIP, REC 100' FO, 60' HO CM, SIP 944-895#, FP 28-38 / 67-76#
B LANS		3943-1553	MICT - CO. PF (LANS) 3874-79, 3914-18 W/4 SPF, ZNS COMMUNICATED, AC 2000G, R&T, POP, P 30 BOPD, 11/27/82
LTD		3957-1567	
RTD		3960-1570	

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS