

4-041788

E-24,818

API Number: 15-065-21,160-0001

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

8-9

SE NW SE /4 SEC. 18, 09 S, 23 W  
1650 feet from S section line  
1650 feet from E section line

Operator license# 5135

Lease: Klenk Well # 5

Operator: John O. Farmer, Inc.

County: Graham 130.65

Address: P.O. Box 352  
Russell, Kansas 67665

Well total depth 4020 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 212 feet  
w/165 sxs.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:30 A.M. Day 9 Month: August Year 1996

Plugging proposal received from: Duane Eickman

Company: John O. Farmer, Inc. Phone:

Were: 4 1/2" casing set at 4018' w/165 sxs cement. Perf. at 3915' - 3964'.

Anhy. at 2078' cwc with 375 sxs.

Ordered 175 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls plus 10 sxs gel.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour 12:00 P.M., Day 9, Month: August, Year: 1996

Actual plugging report: R.U. Cementers squeezed cement down casing as follows: 40 sxs cement with 300# hulls followed with 10 sxs gel, followed with 135 sxs cement. Max. P.S.I. 1000#. S.I.P. 600#. Pressured-up 8 5/8" S.P. Max. P.S.I. 700#.

RECEIVED  
KANSAS CORPORATION COMMISSION

9-6-96  
SEP 06 1996

Remarks: CONSERVATION DIVISION  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC X, NO  
Plugged through TUBING, CASING X. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Rennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE SEP 09 1996  
INV. NO. 46443