

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21547-00-00
Spot: NWSENW Sec/Twnshp/Rge: 18-9S-23W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: ALBERTSON Well Number: 5
County: GRAHAM Total Vertical Depth: 3995 feet

Operator License No.: 5135
Operator Name: FARMER, JOHN O., INC.
Address: PO BOX 352
RUSSELL, KS 67665

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 206
Production: Size 4.5 feet: 3994
Liner: Size feet: 129.84

10/17

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/17/00
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/17/2000 9:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 206' w/165 sxs cwc. 4 1/2" set at 3994' w/150 sxs.
PBD 3964'. Prod. Perf 3888' - 3934'.
Squeezed 4 1/2" w/190 sxs cement with 500# hulls mixed into Max. P.S.I. 1000#. Held.
Tested 8 5/8" w/10 sxs cement blend to Max. P.S.I. 500#. Held.
D.V. Tool at 2064' w/450 sxs cwc. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENT COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow

(TECHNICIAN)

INVOICED

DATE 10/26/00

INV. NO. 2001060890

Form CP-2/3

OCT 23 2000

JOHN O. FARMER, INC. #5 ALBERTSON 18-9-23W
 P.O. BOX 352 RUSSELL, KS 67665 NW SE NW
 CONTR JOHN O. FARMER, INC. CTY GRAHAM

GEOL _____ FIELD ERNST NW

E 2396 KB CM 12/4/81 CARD ISSUED 3/25/82 IP P 4 BO & 5 BWPD

| | | |
|---|---|---|
| - | + | + |
| - | + | + |
| - | + | + |

API 15-065-21,547 LANS 3928-34

| SMP | TOPS | DEPTH | DATUM |
|--------|------|-------|-------|
| ANH | | 2057 | + 339 |
| B ANH | | 2093 | + 303 |
| HEEB | | 3696 | -1300 |
| TOR | | 3722 | -1326 |
| LANS | | 3739 | -1343 |
| TD | | 3995 | -1599 |
| NO LOG | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8 5/8" 206/165sx; 4 1/2" 3994/150sx
 DST (1) 3874-3908/45-45-75-75, 240'g
 60'OCM, SIP 124-171#, FP 47-47/
 66-66#
 DST (2) 3918-3948/30-30-30-30, 25'M
 w/OIL SPOTS, SIP 66-66#, FP 57-57/
 66-66#
 MICT - CO, PF 3888-94, 3928-34, AC
 4000G, R&T, POP, P 4 BOPD & 5 BWPD,
 2/25/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS