

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21780-00-00  
Spot: N2S2N2 Sec/Twnshp/Rge: 21-9S-23W  
3630 feet from S Section Line, 2634 feet from E Section Line  
Lease/Unit Name: GODDARD Well Number: 1  
County: GRAHAM Total Vertical Depth: 4030 feet

Operator License No.: 30076  
Op Name: A & A PRODUCTION  
Address: PO BOX 100  
HILL CITY, KS 67642

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 206 150 SX CMT  
Production: Size 4.5 feet: 4024 450 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/06/2002 1:00 PM  
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION  
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 420 cu.ft. of cement slurry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/06/2002 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 206' w/150 sxs cwc. 4 1/2" set at 4024' w/450 sxs cwc.  
Prod. Perfs 3795' - 3951'. PBTD 3930'.  
Fluid level near bottom. Depleted zone.  
Filled casing with 420 cu.ft. of cement slurry.  
Plug complete.

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 22 2002

CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

INVOICED


Form CP-2/3

FEB 11 2002

DATE Feb 25-02

INV. NO. 2002061409

A. SCOTT RITCHIE                      REPLACEMENT CARD                      21-9-23W  
 125 N. MARKET, SUITE 950                      #1 GODDARD                      C N/2 S/2 N/2  
 WICHITA, KS 67202  
 CONTR H-30 DRILLING, INC.                      CTY GRAHAM  
 GEOL \_\_\_\_\_                      FIELD WC (EVERGREEN WEST DISC)  
 2436 KB  
 ELY 2431 GL SPD 4/28/83                      CARD ISSUED 6/30/83                      IP P 85 BOPD & 15% WTR  
 API 15-065-21,780                      LKC 3795-3951 OA



LOG	Tops	Depth/Datum	
ANH	.....	2033 + 403	DST (1) 3775-3806 (LKC) / 20-30-30-45, REC 725' FROGGY OIL, SIP 899-899#, FP 74-117 / 245-245#, HP 1969-1967#
HEFB	.....	3718-1282	DST (2) 3827-45 (LKC) / 30-45-45-60, REC 470' MW, W/SCUM OIL, SIP 575-575#, FP 53-63 / 181-181#
TOR	.....	3742-1306	DST (3) 3864-3935 (LKC) / 30-45-45-60, REC 200' HOCM (60% OIL), SIP 867-742#, FP 53-63 / 138-138#
LANS	.....	3756-1320	DST (4) 3935-4000 (LKC) / 45-45-45-60, REC 5' FO, 360' MW, W/SCUM OIL, ISIP 669#, ISIP NA, FP 85-85 / 202-202#, IHP NA, FHP 2073#
BKC	.....	3980-1544	MICF - CO, PF (LKC) 3947.5-3951 W/2 SPF, AC 600G, SWB LD, PF (LKC) 1/ 3912 & 1/ 3889.5, AC 1200G, SWB LD, PF (LKC) 3910-13, 3888-91, 3795-3799 W/2 SPF, AC 750G, SWB LD, T&R, POP, P 85 BOPD & 15% WTR, 6/2/83
LTD	.....	4001-1565	
RTD	.....	4030-1594	

COPYRIGHT 1983  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

INFO RELEASED: 8/18/83 - WAS OIL WELL - TIGHT HOLE; ORIGINAL OPERATOR WAS KIOWA EXPLORATION CO. - OPERATIONS TURNED OVER TO A. SCOTT RITCHIE AT CSG PT.  
 NOTE: 5/26/83 - ORIGINALLY FIRST REPORTED AS #1 RIFFEL