

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-193-20,581 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Ellsworth Systems, Inc. KCC LICENSE # 30031
(owner/company name) (operator's)

ADDRESS 922 Union Center Bldg. CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-8844

LEASE Gustafson WELL# 1 SEC. 28 T. 10S R. 33 (~~XXXX~~/West)

N/2 - N/2 SW SPOT LOCATION/QCQQ COUNTY Thomas

2310 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

3960 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 251' CEMENTED WITH 170 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4692' CEMENTED WITH 475 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Pfs: 4595-4610'

ELEVATION 3120 K.B. T.D. 4695' PSTD 4651' ANHYDRITE DEPTH 2610'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Mud & cement as follows: 25 sacks 60/40 Pozmix w/10%

with 300# hulls; 15 sacks gel spacer; 100 sacks 60/40 Pozmix w/10% gel.

Finished with 1200# casing pressure.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ronald S. Schraeder PHONE# (316) 263-0898

ADDRESS 212 N. Market, Suite 405 City/State Wichita, KS 67202

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE #

ADDRESS P. O. Box 31; Russell, KS 67665 (company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) PHONE # ()

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR/AGENT

DATE: June 1, 1994 AUTHORIZED OPERATOR/AGENT: Ronald S. Schraeder

(signature)
Ronald S. Schraeder

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
SEP 08 1994