

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Spiers 'A' Well No. 2-1

Location SE-SE-NW Sec. 29 Twp. 10 Rge. (E) (W) 32

County Thomas Total Depth 4680'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No.       

Operation Completed: Hour 10:30 PM Day 27 Month 11 Year 1974

The above well was plugged as follows:

289'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 110 Cu. Ft. cement  
thru DP from 1675' to 1350'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 12/4/74

INV. NO. 413-W