

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
REVISED  
STATE CORPORATION COMMISSION  
6-24-68  
AUG 31 1977  
8-31-77  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 193 - 20,142 (of this well)

Operator's Full Name Chief Drilling Co., Inc. & Bill J. Porter

Complete Address 905 Century Plaza, Wichita, Kansas

Lease Name Voth Well No. 2 /

Location SE NE Sec. 18 Twp. 10 Rge. (E) (W) 33

County Thomas Total Depth 4780

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 5 P Day 29 Month 8 Year 1977

The above well was plugged as follows:

RTD 4780' 8 5/8 csg set 380' cwc 200 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud set 70 sk cmt plug at 1600' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 8-31-77

INV. NO. 5761-W