

~~KANSAS~~

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas,

Lease Name Albertson Well No. 1

Location SE-SE-SW Sec. 18 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3953'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 12:00 PM Day 4 Month 12 Year 1974

The above well was plugged as follows:

168'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 735'.

Circulated hole with heavy mud. Pulled DP to 960' and displaced 110 Cu. Ft. cement  
thru DP from 960' to 635'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru DP  
from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/13/74  
INV. NO. 456-W

Received  
KCC  
12-9-74

Signed: W. L. Nichols  
Well Plugging Supervisor