

15-065-20169-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Incorporated,  
Complete Address 801 Union Center Building, Wichita, Kansas.  
Lease Name Ernst Well No. 2  
Location CN/2-SW-SW Sec. 20 Twp. 9 Rge. (E) (W) 23  
County Graham Total Depth 4000'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A         
Other well as hereafter indicated         
Plugging Contractor Santa Fe Pipe and Supply, Incorporated,  
Address Box #562, Great Bend, Kansas. License No. 574  
Operation Completed: Hour 11:15 AM Day 7 Month 4 Year 1971

The above well was plugged as follows:

<sup>7" OD</sup>  
~~256'~~ Surface casing, cement circulated with 80 Sx. (6 1/4" Hole).  
2065' ~~4 1/2"~~ casing cemented with 250 Sx. Top of cement @ 825' (Temperature survey).  
Perforations from 1544' to 1780'.

Pushed plug to 1500', sanded back to 1475' and set 3 Sx. cement with dump bailer.  
Pulled 4 1/2" casing and squeezed well initially with 3 sacks hulls and 8 sacks gel and  
followed with 50 Cu. Ft. cement then 7 sacks gel from 800' to 275' and followed with  
60 Cu. Ft. cement from 275' to bottom of cellar. (Mudding and cementing by Sun).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dehals  
Well Plugging Supervisor

INVOICED

DATE 4-12-71  
INV. NO. 3530-W