

KANSAS

2 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Ernst Well No. 1

Location SW-NE-SW Sec. 20 Twp. 9 Rge. (E) (W)23

County Graham Total Depth 3985'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe and Supply, Incorporated,

Address Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 7:30 PM Day 6 Month 4 Year 1971

The above well was plugged as follows:

7" OD.
260'--~~260'~~ Surface casing, cement circulated with --(6 $\frac{1}{4}$ " Hole).
3984'--4 $\frac{1}{2}$ " Production casing cemented on bottom with 125 Sx. Well plugged back to
3955'. Top perforations from 3795' to 3798'.

Punched plug to 3750', sanded back to 3725' and set 3 Sx. cement with dump bailer.

Pulled 4 $\frac{1}{2}$ " casing and squeezed well initially with 3 sacks hulls and 8 sacks gel and

followed with 50 Cu. Ft. cement from 1125' to 800' then 8 sacks gel from 800' to 275'

and followed with 60 Cu. Ft. cement from 275' to bottom of cellar. Maximum pump-in

pressure-200#. Final shut-in pressure-150#. (Mudding and cementing by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 4-12-71
INV. NO. 3529-W