

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Burch Exploration, Limited,

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name Hildebrand Well No. 1

Location SE-SE-SW Sec. 21 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3925

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 6:00PM Day 12 Month 7 Year 1965

The Above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 145 Sx. 3920'--5 1/2"
production casing, cemented with 150 Sx. and Kem-Pac thru Dakotas and to
the surface. Well plugged back to 3875. Top perforations @ 3799'.

Sanded well back to 3730' and set 4 Sx. cement with dump bailer. Pulled 5 1/2"
to 520' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 212' and dis-
placed 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10
Sx. cement to bottom of cellar. (Recovered 1514' 5 1/2" Casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/30/65

INV. NO. 1482-W