

**KANSAS**  
**STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION  
1-19-66

JAN 19 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Specter Pipe and Supply,

Complete Address: P.O. Box #169, Russell, Kansas.

Lease Name Prescott Well No. 1

Location SW-SW-SE Sec. 21 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3975

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Lynch Casing Pulling Company.

Address: Route #4, Great Bend, Kansas. License No. 457

Operation Completed: Hour 11:00AM Day 16 Month 1 Year 1966

The Above well was plugged as follows:

1375' -- 8 5/8" Surface pipe, cement circulated.

3972' -- 5 1/2" Production casing cemented with 150 Sx. Top of cement @ 3425' (Temperature Survey).

Sanded well back to 3965' and set 5 Sx. cement with dump bailer.

Set rock bridge @ 550' and 20 Sx. cement. Filled with mud to 250', set

rock bridge and 20 Sx. cement. Filled with mud to 40', set rock bridge

and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 1/19/66

INV. NO. 2628-4

Signed: M. L. Nichols  
Well Plugging Supervisor