

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE-SF-NW

SEC. 21 TWP. 9 RGE. 23W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Edwards Est.

Operator Heathman & Seeligson Drilling Address 1015 E. 2nd  
Wichita, 7, Kans.

Field \_\_\_\_\_ County Graham

Total Depth 4321' Feet.

Plugging Contractor Banner & Sons Pipe Pulling Co.

Plugging Contractor's License No. 9.

Address Russell, Kans.

(Describe briefly the manner in which the well was plugged)

*Surface pipe 8 7/8" @ 162' c.w.c. 5 1/2" set @ 3980'  
c.w.c. 100'. Plugged back to 3803' & perforated  
from 3795' to 3800' - sand back to 3785' & 5 sp.  
cem. shot 5 1/2" off @ 3403' & pulled same. Filled  
hole w/ heavy mud to 180; set plug & rock bridge  
& 20 sp. cem. w/ dummy bailer. Fill hole w/ mud to  
35' from top, set plug & rock bridge & 10 sp. cem. to  
base of cellar.*

*Milton Gehardt*  
District Conservation Agent

RECEIVED  
PLUGGING CORPORATION COMMISSION  
FILE SEC 21 T 9 R 23W 9-2-55  
BOOK PAGE 146 LINE 42  
CONSERVATION DIVISION

DATE 8-31-55