

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Thomas County. Sec. 15 Twp. 10S Rge. 33 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW

Lease Owner Beren Corporation

Lease Name Gaeddert Well No. 3

Office Address 970 Fourth Financial Center, Wichita KS 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-7 19 77

Application for plugging filed 10-7 19 77

Application for plugging approved 10-7 19 77

Plugging commenced 10-7 19 77

Plugging completed 10-7 19 77

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation Depth to top Bottom Total Depth of Well 4715 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud laden fluid 4715 to 1650'  
70 sks cement @ 1650'  
20 sks cement @ 300'  
10 sks cement @ 40'

RECEIVED  
STATE CORPORATION COMMISSION  
11-4-77  
NOV 04 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations  
Address Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.  
Joe K. Branum (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Joe K. Branum

Box 506, Russell, KS 67665 (Address)

SUBSCRIBED AND SWORN to before me this 11th day of October, 1977

My commission expires October 2, 1979

Notary Public. Patricia L. Clark



EMPHASIS OIL OPERATIONS  
 P. O. Box 506  
 Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Beren Corporation  
 970 Fourth Financial Center  
 Wichita, Kansas 67202

CONTRACTOR: Emphasis Oil Operations  
 Box 506  
 Russell, Kansas 67665

LEASE: Gaeddert WELL: #3

LOCATION: NE SW SW  
 Section 15-10S-33W  
 Thomas County, Kansas

Total Depth: 4715'  
 Commenced: 9-23-77  
 Casing: 8-5/8" @ 340'

Elevation:  
 Completed: 10-7-77  
 Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Surface clay & Sand	290	Anhydrite	2695
Shale	353	Shale	3173
Shale & Shells	525	Shale & Lime	3883
Shale	1585	Lime & Shale	4090
Shale & Sand	2011	Lime	4265
Shale & Lime	2178	Lime & Shale	4295
Shale & Shells	2662	Lime	4715

RECEIVED  
 STATE CORPORATION COMMISSION  
 (R.T.D.)


NOV 04 1977  
 11-4-77  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

*Joe K. Branum*  
 \_\_\_\_\_  
 Joe K. Branum

Subscribed and sworn to before me this 11th day of October, 1977.  
 My Commission Expires: October 2, 1979.



*Patricia L. Clark*  
 \_\_\_\_\_  
 Notary Public