

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Thomas County. Sec. 16 Twp. 10S Rge. 33 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
~~NW $\frac{1}{4}$ SW $\frac{1}{4}$ SE~~ SESESENE


Lease Owner Tanner-Fruit Exploration, Inc.
Lease Name DUMLER Well No. 1
Office Address 1664 Market, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 09-15 1980
Application for plugging filed 09-15 1980
Application for plugging approved 09-15 1980
Plugging commenced 09-15 1980
Plugging completed 09-15 1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas available
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4720'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4720'

Set 1st plug @ 1600' with 70 sx.

2nd plug @ 400' with 20 sx.

3rd plug solid bridge @ 40' with 10 sx.

rathole with 5 sx. cemented with 50/50 posmix, 6% gel

Plug was down @ 6:00 p.m. 09-15-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

RECEIVED
STATE CORPORATION COMMISSION
9-24-80
SEP 24 1980

STATE OF Kansas COUNTY OF Sedgwick
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September, 1980

Jeanette A. Metheny
Jeanette A. Metheny Notary Public.

My commission expires 08-18-84



CONTRACTOR'S WELL LOG

OPERATOR: Tanner-Pruit Exploration, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: DUMLER #1
 LOCATION: ~~NW-NW-NE~~ SE SE SE NE, Section 16-10S-33W
 Thomas County, Kansas
 SPUD DATE: 09-06-80
 COMPLETION DATE: 09-15-80

0	445	Surface Clay, Sand & Shale
445	1040	Clay, Shale & Sand
1040	2000	Shale & Sand
2000	2666	Shale
2666	2698	Anhydrite
2698	2854	Shale
2854	4040	Shale & Lime
4040	4377	Lime
4377	4720	Lime & Shale
	4720	Rotary Total Depth

Spud hole @ 2:30 p.m. 09-06-80. Drilled 445' of a 12-1/4" hole. Ran 11 joints of 8-5/8" 20# casing (tally 435.64') Set at 444'. Cemented with 375 sx. of 60/40 posmix, 3% c.c., 2% gel. Plug was down @ 12:30 a.m. 09-07-80. Cement did circulate.

T.D. 4720'. Set 1st plug @ 1600' with 70 sx., 2nd plug @ 400' with 20 sx., 3rd plug solid bridge @ 40' with 10 sx. Rathole with 5 sx. Cemented with 50/50 posmix, 6% gel. Plugged at 6:00 p.m. 09-15-80.

SAMPLE TOPS:

Anhydrite 2666'
 B/Anhydrite 2698'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1980
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the DUMLER #1, ~~NW-NW-NE~~ SE SE SE NE, Section 16-10S-33W, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 19th day of September, 1980.



Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public