

15-193-20071-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Thomas County, Sec. 26 Twp. 10S Rge. 33W (E) (W)
Location as "NE/CNWxSWx" or footage from lines. C SE NE
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter
Lease Name Alksnis Well No. #1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/16/76 19
Application for plugging filed 1/16/76 19
Application for plugging approved 1/16/76 19
Plugging commenced 1/16/76 19
Plugging completed 1/16/76 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Baltzor, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4690' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| | | 0 | 277' | 8 5/8" | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1600' w/80 sacks cement
Plugged through drill pipe @ 250' w/20 sacks cement
Plugged through drill pipe @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
1-20-76
JAN 20 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jim Robinson*
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1976

My commission expires

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard --
Notary Public.

WELL LOG

CHIEF DRILLING CO., INC.
 905 Century Plaza
 Wichita, Kansas 67202

ALKSNIS #1
 SE NE Sec. 26-10S-33W
 Thomas County, Kansas

CONTRACTOR: Company Tools
 CASING RECORD: 8 5/8" set @ 277' cemented w/180
 sacks common, 2% gel.

COMMENCED: 1/8/76
 COMPLETED: 1/16/76

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>ELEVATIONS</u> |
|------------------|-------------|-----------|-------------------|
| Sand-Shale | 0 | 280 | 3106 Gr. |
| Shale | 280 | 1300 | 3109 D.F. |
| Shale-Sand | 1300 | 2635 | 3111 K.B. |
| Shale | 2635 | 3743 | |
| Lime | 3743 | 4690 | |
| RTD | 4690 | | |

~~FORMATION TOPS~~

ELECTRIC LOG TOPS:

| | | |
|----------------|--------|------|
| Anhydrite | 2623 + | 488 |
| Base Anhy. | 2648 + | 463 |
| Heebner | 4038 - | 927 |
| Toronto | 4058 - | 947 |
| Lansing | 4075 - | 964 |
| Base K.C. | 4367 - | 1256 |
| Marmaton | 4392 - | 1281 |
| Pawnee | 4503 - | 1392 |
| Cherokee Shale | 4592 - | 1481 |
| LTD | 4690 - | 1579 |

RECEIVED
 STATE CORPORATION COMMISSION
 1-20-76
 JAN 20 1976
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SE NE of Section 26-10S-33W, Thomas County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
 Jim Robinson, Vice-President

Subscribed and sworn to before me this 19th day of January, 1976.

MARILYN SINARD
 STATE NOTARY PUBLIC
 SEDGWICK COUNTY, KANSAS
 MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
 Marilyn Sinard - Notary Public