


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Thomas County, Sec. 18 Twp. 10S Rge. (E) 33 (W)
Location as "NE/CNWSW" or footage from lines SE NE
Lease Owner Chief Drilling Co., Inc.
Lease Name Voth Well No. #1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/29/77 19
Application for plugging filed 8/29/77 19
Application for plugging approved 8/29/77 19
Plugging commenced 8/29/77 19
Plugging completed 8/29/77 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4785' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	380'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 1600' w/70 sx. cement
Plugged through drill pipe @ 240' w/20 sx. cement
Plugged through drill pipe @ 40' w/10 sx. cement

RECEIVED
STATE CORPORATION COMMISSION
9-26-77
SEP 06 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK ss.
Jim Robinson (Employer or Owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of September, 1977

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard Notary Public.

My commission expires _____

WELL LOG

15-193-20142-0000

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 Voth
SE NE Sec. 18-10S-33W
Thomas County, Kansas

CONTRACTOR: Company Tools
CASING RECORD: 8 5/8" set @ 380' w/225 sx.

COMMENCED: August 19, 1977
COMPLETED: August 29, 1977

FORMATION	FROM	TO
Surface	0	385
Sand & Shale	385	2625
Shale	2625	2684
Anhy.	2685	2714
Shale	2715	4244
Shale & Lime	4244	4345
Lime	4345	4785
Total Depth	4785	

ELEVATIONS

3173 Gr.
3175 D.F.
3178 K.B.

~~FORMATION TOPS~~

ELECTRIC LOG TOPS:

Anhydrite	2683 +	495
Base Anhydrite	2711 +	467
Heebner	4077 -	899
Toronto	4102 -	924
Lansing	4118 -	940
BKC	4402 -	1224
Marmaton	4429 -	1251
U/Cherokee	4589 -	1411
L/Cherokee	4623 -	1445
Johnson Zone	4675 -	1497
Miss.	4730 -	1552
LTD	4788 -	1610
RTD	4785 -	1607

RECEIVED
STATE CORPORATION COMMISSION
9-6-77
SEP 06 1977
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NE of Section 18-10S-33W, Thomas County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 1st day of September, 1977.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard Notary Public