

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-193-20,267

LEASE NAME Mollie

WELL NUMBER #1

SPOT LOCATION W/2-NW-NE

SEC. 23 TWP. 10 RGE 33 (E) or (W)

COUNTY Thomas

Date Well Completed _____

Plugging Commenced 5-14-86

Plugging Completed 6-9-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR American Energies Corporation

ADDRESS 575 Fourth Financial Center, Wichita, Ks. 67202

PHONE # (316-793-5088) OPERATORS LICENSE NO. 5399

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom T.D. 4780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	345'	None
				4-1/2"	4428'	1,182.64'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4250' and 4 sacks cement. Shot casing at 1800', 1600', 1400' and 1200'. Pulled 29 joints of 4-1/2" casing. B.J. Titan squeezed well with 25 sacks cement, 3 sacks hulls and 175 sacks thrifty-mix cement blended with 2 sacks hulls. Maximum pressure was 500 psi and shutin 300 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1986

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Adpt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman
 Notary Public