

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-193-206640000

LEASE NAME Cooper

WELL NUMBER #1-29

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2210' Ft. from N Section Line

2970' Ft. from E Section Line

SEC. 29 TWP. 10S RGE. 33 <sup>West</sup> ~~East~~

COUNTY Thomas

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS P. O. Box 48848, Wichita, KS 67201-8848

PHONE#(316) 263-1102 OPERATORS LICENSE NO. 5420

Character of Well D & A'

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 8-16-97

Plugging Commenced 8-16-97

Plugging Completed 8-16-97

The plugging proposal was approved on August 16, 1997 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4716'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	359'	none

AUG 21 1997  
8-21-97

CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Spotted 25 sx. cement at 2640' thru drill pipe. Spotted 100 sx. cement at 1725' thru drill pipe. Spotted 40 sx. cement at 410' thru drill pipe. Spotted 10 sx. cement at 40' thru drill pipe. Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White & Ellis Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Michael L. Considine

(Address) P. O. Box 48848  
Wichita, KS 67201-8848

TESTED AND SWORN TO before me this 19th day of August, 19 97

CAROLYN J. TJADEN  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 9-5-2000  
My Commission Expires: 9-5-2000

Carolyn J. Tjaden  
Notary Public  
Carolyn J. Tjaden



15-193-20664-0000

ORIGINAL

# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

15-193-20664

Operator: White & Ellis Drilling, Inc.  
P. O. Box 48848  
Wichita, KS 67201-8848

Contractor: White & Ellis Drilling, Inc.  
P. O. Box 48848  
Wichita, KS 67201-8848

Lease Name Cooper Well No. 1-29  
Spot 100' N of SE SE NW Section 29 Township 10S Range 33W  
County Thomas State Kansas

### Casing Record:

Surface: 8 5/8" @ 359' with 180 sx.  
Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_

Type Well: D & A Total Depth 4716'

Drilling Commenced: 8-7-97 Drilling Completed: 8-16-97

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Tops</u>	
Cellar	0	5	Anhydrite	2618
Sand & Clay	5	2020	B/Anhydrite	2646
Shales, Red Beds	2020	2430	Lansing	4140
Shale & Lime	2430	2995	Kansas City	4240
Shales	2995	3480	"J" Zone	4280
Lime & Shale	3480	3660	Johnson	4630
Shales & Lime	3660	3835	Mississippi	4668
Lime & Shale	3835	4716		

**RECEIVED**  
KANSAS CORPORATION COMMISSION

AUG 21 1997

CONSERVATION DIVISION  
WICHITA, KS