

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Manns' ATP, Inc.
Address: 7865 Northwest 80th Street, Potwin, KS 67123
Phone: (620) 752-3200 Operator License #: 34130
Type of Well: Oil DH KCCPKT Per CP213 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: November 14, 2008 (Date)
by: David Wertz (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 2,177' Bottom: 2,347' T.D. _____
Mississippian Depth to Top: 2,610' Bottom: 2,670' T.D. _____
Kinderhook Depth to Top: 2,670' Bottom: 2,690' T.D. 2,690'

API Number: 15 - 015-23805-00-00
Lease Name: Manns
Well Number: 2
Spot Location (QQQQ): S2 - NE - NE - SW
2,303 Feet from North / South Section Line
2,970 Feet from East / West Section Line
Sec. 26 Twp. 24 S. R. 4 East West
County: Butler
Date Well Completed: November 14, 2008
Plugging Commenced: November 14, 2008
Plugging Completed: November 14, 2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	odor-slight	2,180'	2,190'			
Mississippian	odor-slight	2,635'	2,640'			
Total Depth			2,710'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

35 sacks at 2,660 ft.

35 sacks at 250 ft.

55 sacks at surface (hole not full to top)

Consolidated finished filling surface to top. Shown on enclosed invoices.

KCCPKT
per CP213

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 23 2008

Name of Plugging Contractor: Three Rivers Exploration LLC

License #: 34440 33217 CONSERVATION DIVISION
WICHITA, KS

Address: P.O. Box 884, Chanute, KS 66720


Name of Party Responsible for Plugging Fees: Manns' ATP, Inc.

State of Kansas County, Butler, ss.

Edward Mann, President

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Manns' ATP Inc. By Edward Mann pres.

(Address) 7865 Northwest 80th Street, Potwin, KS 67123

SUBSCRIBED and SWORN TO before me this 19th day of December, 20 08

Donna Manda My Commission Expires: March 16, 2011
Notary Public



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 20321
LOCATION Eureka
FOREMAN Troy Prockler

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-5-08	50ED	Manns #2				Butler
CUSTOMER Manns ATP Inc.			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 7865 NW 80th			520	Cliff		
CITY Potwin			515	Jerrid		
STATE Ks		ZIP CODE 67123				

JOB TYPE S/P HOLE SIZE 12 1/4" HOLE DEPTH 206' CASING SIZE & WEIGHT 854"
CASING DEPTH 200' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 14.8" SLURRY VOL 30 Bbl WATER gal/sk 6.5 CEMENT LEFT in CASING 20'
DISPLACEMENT 11.5 bbl DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: Rig up to 8 5/8" casing. Break circulation w/ 5 bbl water.
Mixed 125psi Class A Cement w/ 3% Cacl2, 2% Gel + 1/4" Floccle @ 14.8#/gal
Displace w/ 11.5 bbl water. Shut casing in w/ Good Cement to surface.
6 bbl slum to pit.
Job Complete

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	725.00	725.00
5406	40	MILEAGE	3.65	146.00
11045	125 skt	Class A Cement	13.50	1687.50
1102	350 #	Cacl2 3%	.75	262.50
1118A	235 #	Gel 2%	.17	39.95
1107	30 #	Floccle 1/4"/sk	2.10	63.00
5407	5.88 Ton	Ton-Mileage	m/c	315.00
RECEIVED KANSAS CORPORATION COMMISSION DEC 23 2008 CONSERVATION DIVISION WICHITA, KS				
<u>Thank You!</u>			Subtotal	3238.95
			5.3% SALES TAX	108.81
			ESTIMATED TOTAL	3347.76

Ravin 3737 02/18/04 AUTHORIZATION _____ TITLE _____ DATE _____

 ENTERED

TICKET NUMBER 20400
 LOCATION EuroKA
 FOREMAN STEVEN BARNAL

CONSOLIDATED
 Oil Well Services, L.L.C.

PO Box 884, Chanute, KS 66720
 820-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-14-08	5500	Manns # 2				Butler
CUSTOMER			TRUCK #		DRIVER	
Manns ATP, Inc			485		Alan	
MAILING ADDRESS			439		Calin	
7865 N.W. 80th						
CITY		STATE	ZIP CODE			
Potwin		KS	67123			

JOB TYPE RTA HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT _____
 CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT In CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting Plug Well As Follow
35 SKS AT 2260'
35 SKS AT 250'
55 SKS 60' TO SURFACE
125 SKS TOTAL 60/40 POZ MIX 4% GEL
Did not get cement to TOP of SURFACE - Following page well top off.
Job Complete Rig down


Thank you

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5406N	1	PUMP CHARGE	926.00	926.00
5406	40	MILEAGE	3.65	146.00
1131	125 SKS	60/40 Pozmix Cement	11.35	1418.75
1118A	430*	Gel 4%	.17	73.10
5407		200 Mileage Bulk Truck	1.53	316.00
RECEIVED KANSAS CORPORATION COMMISSION				
DEC 23 2008				
CONSERVATION DIVISION WICHITA, KS				
			SUBTOTAL	2877.85
			SALES TAX	79.06
			ESTIMATED TOTAL	2956.91

Ravin 3737

001406

AUTHORIZATION Called by Dave Farthing TITLE Tail Pusher DATE _____



TICKET NUMBER 20686
 LOCATION EUREKA
 FOREMAN Rick Latford

PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
12-5-08	5500	Manns # 3				Butler	
CUSTOMER		3 Rivers Exploration		TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS				463	Shannon		
CITY		STATE	ZIP CODE	573	Phillip		
Potwin		KS	67123	436	Chris		

JOB TYPE Surface HOLE SIZE 12 1/4" HOLE DEPTH 210' CASING SIZE & WEIGHT 8 1/2"
 CASING DEPTH 200' g.c. DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 15# SLURRY VOL 30 Bbl WATER gal/sk 6.5 CEMENT LEFT in CASING 20'
 DISPLACEMENT 11 1/2 Bbl DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting - Rig up to 8 1/2" casing. Break circulation w/ 5 Bbl fresh water. Mixed 50% class "A" cement w/ 3% cacl2, 2% gel + 1/4" flocc #1 @ 15# per gal. Displace w/ 11 1/2 Bbl fresh water. Shut casing in w/ good cement returns to surface = 7 Bbl slurry to pit. Job complete. Rig down.

NOTE: Used 20 sks to top off well on Manns # 2

"Thank You"

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5403	1	PUMP CHARGE	725.00	725.00
5406	40	MILEAGE	3.65	146.00
		RECEIVED KANSAS CORPORATION COMMISSION		
11045	125 sks	class "A" cement	13.50	1687.50
1102	3.95#	3% cacl2	.75	262.50
1118A	235#	2% gel	.17	39.95
1107	30#	1/4" flocc #1/sk	2.00	43.00
5407	5.00	ten-mileage bus tax	n/c	315.00
5502C	4 hrs	80 Bbl var. TRK	100.00	400.00
1123	3000 gals	city water	14.00	42.00
11045	20 sks	class "A" cement (topped well off on Manns # 2)	13.50	270.00
		subtotal		3950.95
		SALES TAX		183.35
		ESTIMATED TOTAL		4134.30

Rev'n 3737

221 887

AUTHORIZATION Witnessed by Ed Manns

TITLE Owner

DATE _____