

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McElvain Oil & Gas Properties, Inc.

Address: 1050 17th Street, Suit 1800 Denver, Co. 80265-1801

Phone: (303) 893-0933 X379 Operator License #: 9810

Type of Well: DPDH KCCPKT PERCP2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/12/08 (Date)

by: Ed Schumacher (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163 - 23754 - 00 - 00

Lease Name: Leonard Muir

Well Number: #1-31

Spot Location (QQQQ): NW - SE - SE - NW

2,300 Feet from North / South Section Line

1,970 Feet from East / West Section Line

Sec. 31 Twp. 16 S. R. 17 East West

County: Rooks

Date Well Completed: NA

Plugging Commenced: 11/28/08

Plugging Completed: 11/28/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Dakota	Water	470'	594'	8-5/8", 24#, J-55	Landed at 264'	0'
Cedar Hills	Water	852'	1,052'			
Anhydrite		1,364'	1,408'			
Lansing		3,087'	3,313'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cement plugs were displaced with water while laying down 4-1/2" drill pipe as follows: Plug #1: 25 sx 60/40 Poz from 3,402' to 3,225'

Plug #2: 25 sx 60/40 Poz from 1,375' to ~1,198'. Plug #3: 100sx 60/40 Poz from 870' to ~300'.

Plug #4: 40 sx 60/40 Poz from 300' to ~150'. Plug #5: 10 sx 60/40 Poz from 40' to surface. 30 sx spotted in rat hole and 15 sx in mouse hole.

Note: tops of cement plugs are calculated

Name of Plugging Contractor: Allied Cementing Co., LLC - American Eagle Drilling LLC License #: 20-6975804 33493

Address: P.O. Box 31 Russell, Kansas 67665 KCCPKT PER

Name of Party Responsible for Plugging Fees: McElvain Oil & Gas Properties, Inc. CP2/3

State of Colorado County, Denver, ss.

James Marshall McKinney, Jr. (Employee of Operator) or (Operator) on above-described well is duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as follows and the same are true and correct, so help me God.

(Signature) J.M. McKinney, Jr.

(Address) 1050 17TH STREET, SUITE 1800, DENVER, Co. 80265

SUBSCRIBED and SWORN TO before me this 18 day of DECEMBER, 2008

DEBORAH K. POWELL
NOTARY PUBLIC
STATE OF COLORADO

Debra K Powell My Commission Expires: _____
Notary Public

Address to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

My Commission Expires 04/11/2010

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 22 2008

[Handwritten initials]