

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: TriUnited Investors, LLC
Address: 2149 Vizcaya Circle, Campbell, CA. 95008
Phone: (408) 888-1088 Operator License #: 33636
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 2, 2008 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: 2815 Bottom: 3149 T.D. 3158
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-19168-00-00
Lease Name: Ruby
Well Number: 2
Spot Location (QQQQ): _____ - SE - NW - NE
4290 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 36 Twp. 14 S. R. 13 East West
County: Russell
Date Well Completed: 9/15/1950
Plugging Commenced: 11/24/2008
Plugging Completed: 11/25/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
L/KC	Oil	2839'	2950'	8 5/8"	205'	None
				4 1/2"	3158'	None
				3 1/2"	3158'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated both 3 1/2" and 4 1/2" casing @ 1550', 650' and 200'.

RIH w/tbg to 2800', spot 3 sxs of gel, 40 sxs cement with 200 lbs hulls.

Pulled tubing to 1550' & spot 210 sxs cement with 100 lbs hulls. Pulled all tubing and SDON.

11/25/2008 tagged cement w/tbg @ 750' and circulated with 40 sxs cement. Pulled tbg, tied to annulus and circ w/75 sxs cmt. Plug down @ 11:30 AM.

Name of Plugging Contractor: Super Oil Well Service, Inc. License #: 33930

Address: PO Box 519, Russell, KS. 67665

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: TriUnited Investors, LLC

State of California County, Snata Clara, ss.

Terry McCarthy (Employee of Operator) or (Operator) on above-described well which has first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Roger Z. Moses

(Address) PO Box 385, Hays, KS. 67601

SUBSCRIBED and SWORN TO before me this 29 day of December, 20 08

Jim Kronewitter Notary Public My Commission Expires: 1-14-2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



[Handwritten initials]