

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R & B Oil & Gas Inc

Address: PO Box 195, Attica, KS 67009

Phone: (620) 254-7251 Operator License #: 31191

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Jeff Klock (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 4440 Bottom: 4450 T.D. 4834

API Number: 15 - 077-20, 611 - 00 - 00

Lease Name: Muir C

Well Number: 1

Spot Location (QQQQ): 80 N - SE - SE - NW

410 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 22 Twp. 31 S. R. 9 East West

County: Harper

Date Well Completed: 9-10-80 spud

Plugging Commenced: 9-18-08

Plugging Completed: 9-30-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	326	
Miss	Oil/Gas	4440	4450	4 1/2	4834	2680

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4380', bailed 4 sacks with bailer, pulled slips, had 24" stretch, ripped casing at 3010', worked pipe, ripped casing at 2840', worked pipe, ripped casing at 2680', came free, pulled up to 1500', pumped 35 sacks, pulled to 900', pumped 35 sacks, pulled to 370', pumped 110 sacks to surface, pulled rest of casing, well blew some cement out of 8 5/8", packed casing head back together, hooked up to 4 1/2" nipple, pumped 25 sacks cement, shut in, pumped 10 sacks down casing, max pressure 1750 psi, shut in, pressure 15 psi.


Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.

State of Kansas County, Harper, ss.

Dustin Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 **JANE SWINGLE**
Notary Public - State of Kansas
My Appt. Exp. 1-6-2011

(Signature) Dustin Newberry

(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED and SWORN TO before me this 24th day of December, 2008

Jane Swingle My Commission Expires: 1-6-2011
Notary Public, Jane Swingle

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2008
CONSERVATION DIVISION
WICHITA, KS

KCC
per
CP23

PKT

QUALITY OILWELL CEMENTING, INC.

No. 2226

Phone 785-483-2025
Fax 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

9-22-08	Sec. 22	Twp. 31	Range 9	Called Out	On Location	Job Start 1:30	Finish 4:00
Music C		Well No. 1	Location 7S 1/2 W of Zenda		Harper County	KS State	
Contractor Quality Well Service				Owner			
Job Plug				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Size 4 1/2		T.D.		Charge To B + B oil + Gas			
Size		Depth		Street			
Size		Depth		City State			
Size		Depth		The above was done to satisfaction and supervision of owner agent or contractor.			
Left in Csg.		Shoe Joint					
Max.		Minimum					
Size		Displace		CEMENT			
EQUIPMENT				Amount Ordered 215 SKS 60/40 4%			
Truck 6	No.	Cementer Dave		Consisting of			
Truck 7	No.	Driver Rich		Common			
Truck	No.	Driver Jerome		Poz. Mix			
JOB SERVICES & REMARKS				Gel.			
Truck Charge				Chloride			
Rate 35				Hulls 200 #			
Rate				Salt			
Total				Flowseal			
Trucks				Sales Tax			
35 pumped 35 SKS @ 1500				Handling			
35 pumped 35 SKS @ 900				Mileage			
35 pumped 110 SKS @ 370 to surface				Sub Total			
				Total			
13-08 pumped 25 SKS down 4 1/2				Floating Equipment & Plugs			
Supply Shut well in				Squeeze Manifold			
				Rotating Head			
12-08 pumped 10 SKS down csg							
Max pressure 1750 psi							
Set in 1500 psi							
				Tax			
				Discount			
Signature David Braden				Total Charge			

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2008
CONSERVATION DIVISION
WICHITA, KS