

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hawkins Oil LLC
Address: 427 S Boston Ave. Suite #915
Phone: (918) 382-7743 - Operator License #: 32693
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/12/08 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Admiral Sand Depth to Top: 704 Bottom: 734 T.D. 769

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 015-23660 - 00-00
Lease Name: Girod B
Well Number: 5 - A KCCPTM CP2/3
Spot Location (QQQQ): SW - SE - SW -
330 Feet from North / South Section Line
840 Feet from East / West Section Line
Sec. 25 Twp. 25 S. R. 4 East West
County: Butler
Date Well Completed: 12/11/04
Plugging Commenced: 12-12-08
Plugging Completed: 12-12-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	surf.	208	8 5/8	208	0
	Production	Surface	776	5 1/2	776	408

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 670' dump bail mix and dump 2 sacks of cement on plug with dump bailor , Pull stretch on casing shoot off at 408' pull pipe to 270' circulate 120 sax 60/40 poz to surface pull pipe top hole off with cement

Name of Plugging Contractor: Barrco Operating Company License #: 3009
Gressel Oil Field Service, Inc. License #: 3009
Address: Box 438 Haysville Ks 67060

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 22 2008
CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Hawkins Oil LC
State of Kansas County, Sedgwick, ss.
R A Schremmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) _____

Patricia Vandebrounhorst
Notary Public - State of Kansas
My Appt. Expires 12/31/2011

SUBSCRIBED and SWORN TO before me this 15 day of December, 2008
Patricia Vandebrounhorst My Commission Expires: 12/31/2011
Notary Public