

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,544-0000

LEASE NAME Nye A

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4780' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 36 TWP. 9S RGE. 32 (E) or (W)

COUNTY Thomas

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P.O. Box 780407, Wichita, KS 67278

PHONE# (316) 685-1441 OPERATORS LICENSE NO. 5131

Date Well Completed _____

Character of Well D&A

Plugging Commenced 2-26-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-27-91

The plugging proposal was approved on 2-27-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top _____ Bottom _____ T.D. 4740'

Show depth and thickness of all water, oil and gas formations.

STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

MAR 28 1991

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 344' | None |
| | | | | | | |
| | | | | | | |

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud; set 1st plug 2650'-2550' w/25 sx; 2nd plug 1800'-1400' w/100 sx; 3rd plug 400'-240' w/40 sx; 4th plug 40'-surface w/solid bridge w/wiper plug & 10 sx; Rathole 15 sx; 190 sx 60 40 permix 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 91

Angela Woodard
Notary Public

My Commission Expires: 3-20-93