

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2009
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cabot Oil & Gas Corporation
Address: 600 17th Street, Ste. 900N, Denver, CO 80202
Phone: (303) 226-9400 Operator License #: 6120
Type of Well: Gas D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 12-29-08 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Chase - Dry Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 175-22091 - 00 - 00
Lease Name: Metcalf
Well Number: 3-7
Spot Location (QQQQ): _____ - SE - SE - SW
330 Feet from North / South Section Line
2248 Feet from East / West Section Line
Sec. 7 Twp. 34 S. R. 33 East West
County: Seward
Date Well Completed: 1-11-08
Plugging Commenced: 12-30-08
Plugging Completed: 12-30-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Herrington	Dry	2,636'	2,640'	8-5/8"	1,512'	None
U. Krider	Dry	2,664'	2,668'	4-1/2"	3,215'	628'
L. Krider	Dry	2,698'	2,727' (OA)			
Winfield	Dry	2,760'	2,766' (OA)			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300# hulls & 15 sx cmt to plug perf's from 2636 to 2436, mud spacer to 1600 & mixed

20 sx plug 1600 to 1330, Mud to O.Shot & pulled 4-1/2 to 550. Circulate hole w/ mud & mixed 40 sx 550 to 430, 10 sx 40 to 0, capped 8-5/8" 3' below GL

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151
Address: Rt. 1, Box 49 BA, Tyrone, OK 73951-9731 PH#: 580-854-6515
Name of Party Responsible for Plugging Fees: Cabot Oil & Gas Corp, 600 17th St, Ste. 900N, Denver, CO 80202
State of Colorado County, Denver, ss.

Jean Arnold - Prod. Tech. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jean Arnold
(Address) Cabot Oil & Gas Corp., 600 17th St., Ste. 900N, Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 6th day of January, 20 09
KATHRYN B. FLAGER
NOTARY PUBLIC
STATE OF COLORADO
Kathryn B. Flager My Commission Expires: 11-12-2011
Notary Public
My Commission Expires 11/12/2011 - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT