

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-4
December 2003

JAN 05 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

CONSERVATION DIVISION
WICHITA, KS

Lease Operator: Lotus Operating Co. LLC
Address: 100 S. Main Ste 420, Wichita, Kansas 67202
Phone: (316) 262-1077 Operator License #: 31980
Type of Well: ENHR Docket #: E-28102
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-1-2008 (Date)
by: Steve Bond (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-155-21329-00-01
Lease Name: Royce A
Well Number: 2
Spot Location (QQQQ): NW - SW - SE
990 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 16 Twp. 25 S. R. 9 East West
County: Reno
Date Well Completed: 8/19/1994 original dt.
Plugging Commenced: 6/5/2008
Plugging Completed: 6/9/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	228	8 5/8	228	0
		0	4139	5 1/2"	4139	2390'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Casing shot off at 2390'. Basic Energy Services set 1st plug @ 1463' w/ 35 sx, 2nd plug @ 777' w/ 35 sx, 3rd plug @ 291' w/ 130 sx. Cement circulated to 190'.

Basic Energy Services cemented from 190' to surface w/ 100 sx. All cement used was 60/40 poz mix.

Name of Plugging Contractor: Bronco Energy Services License #: 5096 / 7407 KCCPT part license
Address: 6601 SW 29th Street, Oklahoma City, OK. 73179
Name of Party Responsible for Plugging Fees: Lotus Operating Co. LLC
State of Sedgwick County, Kansas, ss.

Lotus Operating Co. LLC (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 100 S. Main Ste 420; Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 02 day of January, 20 09
Vicki L. Lovett My Commission Expires: 4-18-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

