

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION

JAN 05 2009

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

CONSERVATION DIVISION
WICHITA, KS

Lease Operator: Herman Loeb

Address: PO Box 838 Lawrenceville, IL 62439

Phone: (618) 943-2227 Operator License #: 3273

Type of Well: gas well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/08/2008 (Date)

by: Ken (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: 2640 Bottom: 2656 T.D. 2860

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-171-20127-0000

Lease Name: Petro

Well Number: 1-2

Spot Location (QQQQ): _____ - _____ - C - NE

1320 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 2 Twp. 20 S. R. 33 East West

County: Scott

Date Well Completed: 11/02/1976

Plugging Commenced: 12/08/2008

Plugging Completed: 12/12/2008

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|------|-------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Chase | | surface | 370 | 8 5/8 | | |
| | | surface | 2859 | 4 1/2 | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set castiron plug @ 2550, set 2nd plug @ 1310. Pressure test casing to 750 psi, held pressure. Perferated well @ 1275 3 shots & 1225 set cement retainer @ 1200, run tubing in sting into retainer pump 80 sacks 60/40 4% gel. Pull out of retainer pump 65 sacks to surface, pumped 35 sack down backside to 500 psi.

Name of Plugging Contractor: Eastern Colorado Well Service License #: 32997

Address: PO Box 244, Cheyenne Wells, Co 80810

Name of Party Responsible for Plugging Fees: Herman Loeb

State of Colorado County, Cheyenne, ss.

Shane Pelton (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) Box 792 Cheyenne Wells Co 80810

SUBSCRIBED and SWORN TO before me this 31st day of December, 20 08

Ray Dyer My Commission Expires: 8-10-2011

Notary Public

4307962005
Cheyenne Wells Co 80810
Mail to: KCC Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]