

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mull Drilling Company, Inc.
Address: P.O. Box 2758, Wichita KS, 67201-2758
Phone: (316) 264-6366 Operator License #: 5144
Type of Well: D&A Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/20/08 (Date)
by: David Wann (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 063-21759-00-00
Lease Name: Coberly
Well Number: #1-2
Spot Location (QQQQ): SE/4 - NE/4 - NW/4 - SE/4
2008 Feet from North / South Section Line
1388 Feet from East / West Section Line
Sec. 2 Twp. 15 S. R. 28 East West
County: Gove
Date Well Completed: 11/25/08
Plugging Commenced: 11/25/08
Plugging Completed: 11/25/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	224'	8 5/8"	217.68'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

25 sx @ 1960'; 100 sx @ 915'; 40 sx @ 275'; 10 sx @ 40'; 30 sx rathole; 15 sx mousehole. By Allied.

220 sx total 60/40 poz, 4% gel, 1/4# flo-seal. Drilling mud was placed between stages.

Name of Plugging Contractor: WW Drilling, LLC License #: 33575
Address: P.O. Box 307, WaKeeney KS 67672
Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.


RECEIVED
KANSAS CORPORATION COMMISSION

JAN 08 2009

Mark A. Shreve, President/COO (Employee of Operator) or (Operator) on above described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 2758 Wichita KS 67201-2758



SUBSCRIBED and SWORN TO before me this 7th day of January, 20 09

Tannis L. Tritt My Commission Expires: 3-26-2011
Notary Public

WW Drilling, LLC
WaKeeney, KS
Well Plugging Orders

Operator: Mull Drilling Company, Inc. License # 5144
Address: 221 N Main Ste 300, PO Box 2758 Wichita KS, 67202

API # 15-063-21759-00-00

Lease Name: Coberly #1-2
Legals: 2008 FSL & 1388 FEL, Section 2-15s-28w
County: Gove
State: KS

Plug #	Sx.	@	Feet
1st	<u>25</u>	<u>@</u>	<u>1960</u>
2nd	<u>100</u>	<u>@</u>	<u>915</u>
3rd	<u>40</u>	<u>@</u>	<u>275</u>
4th	<u>10</u>	<u>@</u>	<u>40</u>
5th		<u>@</u>	
Rathole	<u>30</u>		
Mousehole	<u>15</u>		

Total: 220

Type: 60/40 Poz - 4% Gel - 1/4 # per sx flo-seal

Spud Report: Ray Dinkel Date: 11/17/2008 Time: 9:15 AM
Orders From: David Wann Date: 11/20/2008 Time: 9:00 AM
Reported to: Case Morris Date: 11/26/2008 Time: 9:15 AM
Results: D & A

RECEIVED
KANSAS CORPORATION
JAN 08 2009
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

28941

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Ness City KS

DATE 11-25-09	SEC. 2	TWP. 15s	RANGE 28w	CALLED OUT 11:30 AM	ON LOCATION 400 PM	JOB START 600 PM	JOB FINISH 700 PM
LEASE Cab-17	WELL# 1-2	LOCATION Paw Darnis To Pawnee RD			COUNTY Gove	STATE KS	
OLD OR <u>NEW</u> (Circle one)			13 North 1 west south into				

CONTRACTOR w-w- Drilling R-2 OWNER Mull Drilling Co.

TYPE OF JOB Rotary Plug

HOLE SIZE 7 3/4 T.D. 4400 CEMENT

CASING SIZE 4 1/2 DEPTH 1960 AMOUNT ORDERED 220SK 60/40 4% gel

TUBING SIZE DEPTH 5 fl seal

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT

EQUIPMENT

PUMP TRUCK CEMENTER wayne-D

181 HELPER Gallie-D

BULK TRUCK

344-170 DRIVER Jack B

BULK TRUCK

DRIVER

REMARKS:

1st Plug 1960 mix 250X - 3.98 BBLs
 2nd Plug 915 mix 100X - 15.95 BBLs
 5 BBLs freshwater Displacement
 3rd Plug 275 mix 400X - 6.38 BBLs Displacement
 4th Plug 40 mix 100X - 1.59 BBLs Displacement
 Rat mix 300X - 4.78 BBLs Displacement
 Mouse 150X - 2 BBLs
 wash up Ris Down

CHARGE TO: Mull Drilling

STREET

CITY STATE 4.78 ZIP

15 SK - 2 BBL

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Lonnie Lang

PRINTED NAME Lonnie Lang

COMMON @

POZMIX @

GEL @

CHLORIDE @

ASC @

@

@

@

@

@

@

@

@

@

@

@

@

@

HANDLING @

MILEAGE @

TOTAL

20 BBLs Ris mud

5 freshwater Displacement

SERVICE

DEPTH OF JOB 1960

PUMP TRUCK CHARGE

EXTRA FOOTAGE @

MILEAGE @

MANIFOLD @

plug Pin Rent @

@

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 08 2009
TOTAL

CONSERVATION DIVISION
WICHITA, KS

PLUG & FLOAT EQUIPMENT

@

@

@

@

@

TOTAL

TAX

TOTAL CHARGE

DISCOUNT IF PAID IN 30 DAYS