

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

01 KCC 1-7-09

API # 15 - 007-22477 - 00-~~08~~ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 7/26/1995

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334
(Owner / Company Name) (Operator's)

Address: P.O. Box 18496 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 879 - 9375

Lease: Wheat A Well #: 2-34 Sec. 34 Twp. 33 S. R. 14 East West

 - NW - SW - SE Spot Location / QQQQ County: Barber

800 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2190 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" 24# Set at: 1,099 Cemented with: _____ Sacks

Production Casing Size: 5 1/2" 14# Set at: 5,243 Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: Bridge plug @ 4,341'

Douglas - 3,936 - 3,942; Mississippian - 4,708 - 4,734; 4,774 - 4,790.

Elevation: 1,660 (G.L. / K.B.) T.D.: _____ PBTD: 5,146 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See Attachment

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

OCT 09 2008

If not explain why? _____

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bud Neff, Production Superintendent Phone: (620) 277 - 0803 ext. 11

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996 AKCC
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/7/2008 Authorized Operator / Agent: Doug Hewitt by Aletha Dumbre-King
(Signature)

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DW 1
PKA

Wheat A 2-34
34-33S-14W
Barber Co., KS

Procedure:

Plug and Abandon:

1. MIRU workover unit. PU SN, setting tool, and 5 ½" CIBP. TIH on 2-3/8" tubing and space out to land CIBP at ±3,925'. TOOH, SB tubing, LD setting tool. Dump 2 sacks of cement on CIBP.
2. Weld pulling sub on 5 ½" casing. MIRU wireline and perform free-point inspection and cut off 5 ½" casing ±50' above free-point. POOH with free-point tools and RDMO wireline.
3. TOOH, LD 5 ½" casing in singles. PU 2 3/8" tubing and TIH open-ended to casing stub. Load hole with 9.0 ppg plugging mud.
4. MIRU cementing services mix and pump 40 sacks of cement, displaced with plugging mud.
5. PU and land EOT at ±1,150'. Mix and pump 50 sack cement plug, displacing with plugging mud.
6. PU and land EOT at ±40'. Mix and pump 25 sack cement plug.
7. RDMO cementing services. TOOH, LD 2-3/8" tubing in singles. Cut off 8 5/8" casing 4' below ground level. Weld on ID cap and clean up location.
8. Send 5 ½" casing, 2-3/8" tubing, ¾" API-D rods, pumping unit, 300 bbl steel production tank, and meter run in to be inspected and salvaged. RDMO workover unit.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 09 2008

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHESAPEAKE OPERATING, INC.
6200 N WESTERN AVE
PO BOX 18496
OKLAHOMA CITY, OK 73118-1046

October 14, 2008

Re: WHEAT A #2-34
API 15-007-22477-00-~~00~~01 *kcc ap*
34-33S-14W, 800 FSL 2190 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 12, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888