

12-29  
4-041441

19R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-22,838-00-00

NE NW SW /4 SEC. 27, 11 S, 15 W  
2310 feet from S section line  
4290 feet from E section line

Operator license# 5140 Lease Abbott well # 1

Operator: Frontier Oil Company County Russell

Address: 125 N. Market Well total depth 3325 feet <sup>108.06</sup>  
Suite 1720 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67230 Surface pipe 8 5/8 Inch @ 207 feet  
w/140 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:00A.M. Day: 29 Month: December Year: 92

Plugging proposal received from: Richard Parker

Company: Frontier Oil Company Phone: 913-483-5348

Were: 4 1/2" casing set @ 3320' w/150 sx. cement. Perf. 3196' -  
3308'. D.V. @ 906' w/300 sx. circ. cement. W.L.M. 3300'.  
Order 250 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 10:00A.M., Day: 29, Month: December, Year: 92

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 250 sx.  
cement with 1/4# flocele plus 300# hulls mixed in cement.  
Max. 800# P.S.I. S.I. 100# P.S.I. Hooked-up to 8 5/8" S.P.  
Pressured-up to 500# P.S.I.

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO  
Bottom plug(in place):YES X ,CALC X ,NO Dakota plug:YES X NO  
Plugged through TUBING CASING X . Elevation:    

RECEIVED  
STATE CORPORATION COMMISSION  
F14-1993  
JAN 14 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS

I did X did not     ] observe the plugging. Dennis L. Hamel

DATE 1-25-93  
WELL NO 37227

(agent)  
Form CP-2/3