

12-29

20 R

4-041440

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-22,843-00-00

NW NW SW /4 SEC. 27, 11 S, 15 W
2310 feet from S section line
4950 feet from E section line

Operator license# 5140 Lease Abbott well # 2

Operator: Frontier Oil Company County Russell

Address: 125 N. Market Well total depth 3401 feet
Suite 1720 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67230 Surface pipe 8 5/8 Inch @ 207 feet
w/140 sx.

H0.53

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:00A.M. Day: 29 Month: December Year: 92

Plugging proposal received from: Richard Parker

Company: Frontier Oil Company Phone: 913-483-5348

Were: 4 1/2" casing set @ 3400' w/150 sx. cement. Perf. 3214' -
3220'. D.V. @ 928' w/300 sx. circ. cement.
Order 250 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 11:00A.M, Day: 29, Month: December, Year: 92

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 250 sx.
cement with 1/4# flocele plus 300# hulls mixed in cement.

Max. 1000# P.S.I. S.I. 500# P.S.I. Hooked-up to 8 5/8" S.P.

Pressured-up to 550# P.S.I.

RECEIVED
STATE CORPORATION COMMISSION
1-14-1993
JAN 14 1993
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] did not [] observe the plugging. Dennis L. Hamel

DATE 1-25-93

WV. NO 37226

(agent)
Form CP-2/3

HP