

6 020508

6-3

API NUMBER 15- 167-22,853-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 50'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E NW NE SW SEC. 27, T 11 S, R 15 W/E
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Abbott Well # 5
County Russell 107.25

Operator: Frontier Oil Co.
Name & Address: 125 N. Market Sta 1720
Wichita, Kansas

Well Total Depth 3300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 238 w/140 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger License Number 5302

Address _____

Company to plug at: Hour: _____ Day: 31 Month: May Year: 19 89

Plugging proposal received from Walter Oden

(company name) Red Tiger (phone) 5302

were: Order 175 sks 60/40 poz 6% gel 3% cal cl 1/2 sk f.c. per sk and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION

6-13-1989
JUN 13 1989

Plugging Proposal Received by _____

CONSERVATION DIVISION (TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30AM Day: 3 Month: June Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3218' w/25 sks 50' above abr.

2nd plug at 900' w/25 sks

3rd plug at 500' w/100 sks

4th plug at 40' w/10 sks w/wiper

15 sks in rathole

Remarks: Allied

(if additional description is necessary, use BACK of this form.)

INVOICED (operator did not observe this plugging.)

DATE 6-14-89

INV. NO. 25058

Signed Gilbert Balthazor (TECHNICIAN)

Gilbert Balthazor